BRUHAT BANGALORE MAHANAGARA PALIKE

O/o, Executive Engineer (MPED-C), N.R.Square, BBMP, Bengaluru-560002

No. E.E/MPED(C)/QTN/ 02/2023-24
Dated: 04.12.2023

SHORT TERM QUOTATION NOTIFICATION FOR RATES

The quotation are invited from the reputed agencies / Suppliers / Distributors /Contractor for the work of **Construction of fire Escape staircase with fire fighting works for Annex-3 building at BBMP Head office Bengaluru** The interested supplier/agencies are requested to submit/upload their quotation **through KPP-Portal** on before **12.12.2023 at 5:30 pm** as detail in the table indicated below, the quotation shall be opened on **13.12.2023 at 5:30PM.**

Sl.	Particulars	Unit	Qty
1	Double Leaf doorset - Insulated Fire rated doorset (FD 120) - Staircase / exit pathway application / Refuge area. Providing and fixing of ISI marked fire doors as per IS 3614:2021, 120 minutes fire rating with 30 minutes insulation double leaf doorset tested to IS/ISO 3008. Doorset shall include grooved step frame profile of 125x75mm, made of 1.2mm GI (120GSM) and 60mm thick shutter made of 1.2mm GI (120GSM) with infill of 120kg density mineral wool. Grooved frame shall include EPDM smoke seal. Include hardwares, minimum 6nos SS ball bearing hinges of SS304 100x89x3mm, 1no of Single point Panic device and external trim with key cylinder on active leaf and 1no two point Panic device on the inactive leaf, tested as per EN1125 and CE marked. 2no of Door closer with spring size of EN 3-5, as per EN1154 and CE marked. 1no door coordinator for sequencing. 2nos vision panel 200 x 300 with 6mm clear fire rated glass and finished in desired colour of powder coating not less than 50microns including suitable anchors & fire rated puff grouting all inclusive for fixing of doorset - for	SQM	**1.00**

Sl.	Particulars	Unit	Qty
	staircase / exit pathway / Refuge area applications.		
2	Air circulators of 48" dia and 40'.0" air throw,the air circulator shall be fixed with necessary angle iron bracket and other fixing accessories.	EACH	**1.00**
3	Providing and installing in position the following type of sign boards made out of 3mm thick "Opaque" PVC foam board with computer cut, PVC non-reflective self adhesive vinyle painted foam board, ocmplete with mirror fasteners. Providing and installing in position the following Signage printed with "IN CASE OF FIRE, USE STAIRS UNLESS INSTRUCTED OTHERWISE" of 1.25cm height letters in red with white back ground. The size of the board shall be 25cm x 25cm and shall be fixed at the height of 2mts. From finished floor near Manual Call Point.	EACH	**1.00**
4	Providing and installing in position the following type of sign boards made out of 3mm thick "Opaque" PVC foam board with computer cut, PVC non-reflective self adhesive vinyle painted foam board, ocmplete with mirror fasteners. Providing and installing in position the following Floor indentification signage GROUND FLOOR TO 6TH FLOOR. at each stair enclosure on every floor, indicating the floor number in words, lettering size shall be 5cm with contrasting colour from back ground. Size shall be 15cm x 30 cm.	EACH	**1.00**
5	Providing and installing in position the following type of sign boards made out of 3mm thick "Opaque" PVC foam board with computer cut, PVC non-reflective self adhesive vinyle painted foam board, ocmplete with mirror fasteners. Providing and installing in position the following Exit sinage FIRE EXIT at each stair enclosure on every floor, indicating the direction of exit, lettering size shall be 7.5 cm with contrasting colour from back ground. Size shall be 15cm x 60cm.	EACH	**1.00**
6	Providing and installing in position the following type of sign boards made out of 3mm thick "Opaque" PVC foam board with computer cut, PVC non-reflective self adhesive vinyle painted foam board, ocmplete with mirror fasteners. Assembly area signage at Stilt floor, indicating the location of assembly in case of fire emergency, lettering size shall be 12.5 cm with contrasting colour from back ground. Size shall	EACH	**1.00**

Sl.	Particulars	Unit	Qty
	be 30cm x 45cm.Supply & Installation.		

TERMS AND CONDITIONS:

1. The agency shall quote the rate as per the specification and drawing prescribed.
2. The rate quoted shall be inclusive of all materials, labour, fabrication, transportation etc…, excluding GST
3. The quotations are invited for the purpose of budgetary offer for adopting rates in the estimate.
4. The agencies do not have any claim for entrustment of work.
5. Any other information shall be had from the office of the under signed during office hours or **Contact No.9986306614**
6. BBMP reserves right to accept or reject the quotation part or all without assigning any reasons.

-sd/-
Executive Engineer (MPED-C)
Bruhath Bangalore
Mahanagara Palike

COPY SUBMITTED TO:-

1. Personnel Secretary to Hon'ble Administrator to bring into the kind notice of the Hon'ble Administrator.
2. Personnel assistant to Hon'ble Commissioner for kind information.
3. Special Commissioner (Projects)/ Special Commissioner (Finance) for kind information
4. Engineer – in – Chief for kind information.
5. Chief Engineer (Project-Central) for kind information.
6. CAO / Chief Auditor for kind information.
7. I. T. Advisor with a Request to publish the same in the BBMP Website.
8. Public Relation Officer, BBMP for information and to publish in two leading National Newspapers in Kannada and English.
9. Notice board & Office Copy.

Executive Engineer
MPED-CENTRAL
Bruhat Bangalore Mahanagara
Palike